

యోగి వేమన విశ్వవిద్యాలయం
YOGI VEMANA UNIVERSITY
 Vemanapuram, Kadapa - 516003, Andhra Pradesh, INDIA.
 (తన్నుతానెరిగిన తానెవో బ్రహ్మంబు :: If know thyself, Thou Art the Divinity)

ఆచార్య కె. చంద్రయ్య, M.Sc., M.Phil., Ph.D.,
 కులసచివులు
 Prof. K. Chandraiah, M.Sc., M.Phil., Ph.D.,
 REGISTRAR



☎ 08562 -225429
 Fax : 08562 -225419
 98858 07919
 94900 83127
 ✉ registryvu@gmail.com
 chandraiah2002@yahoo.co.uk
 kchandraiah@svuniversity.ac.in

No.YVU/ Engg.Dept/UE/JTO/Car Parking shed at Arts & Commerce Building/web
 Quotation/2018-19 Dt. 25-02-2019

From
The Registrar
 Yogi Vemana University
 Kadapa

Sub:- Y.V.U- Engineering Section –Engineering Department- **Construction of Car Parking shed at New Arts & Commerce Building in Yogi Vemana University, Kadapa** – Permission to call for the quotations thorough University Web site - Request - Reg.

Ref:- Orders of the Hon'ble Vice Chancellor dated : 25-02-2019

-o0o-

The eligible Contractors/firms are requested to send their lowest quotation towards **“Construction of Car Parking shed at New Arts & Commerce Building in Yogi Vemana University, Kadapa”** the quotation should be addressed to the Registrar, Yogi Vemana University, Kadapa to reach this office on or before 28-02-2019.

S.No	Description of Item	Quantity	per	Rate	Amount
1.	Earth work excavation for foundations (Mechanical Means) for buildings in ordinary soils and depositing on bank for all lifts and with an initial lead of 10m and 3m to 6m depth including all operational, incidental, labour charges such as shoring, sheeting, planking, strutting etc., and complete for finished item of work excluding dewatering charges etc., as per SS 20 B(APSS 308)	67.80	Cum		
2.	Filling with carted gravel in trenches, sides of foundations and basement with initial lead in layers not exceeding 15cm thick, watering and ramming including cost and conveyance of water to work site and all operational, incidental, labour charges, hire charges etc, complete for finished item of work(APSS NO.309&310)	19.54	Cum		
3.	Plain Cement Concrete (1:5:10) (cement: fine aggregate: Coarse aggregate) for foundations and under flooring bed using coarse aggregate 40mm size hard, machine crushed granite from approved quarry including cost and conveyance of all materials like cement, sand, coarse aggregate, water etc. to site, sales & other taxes on all materials and including all charges for machine mixing, laying concrete in foundations and under flooring bed, ramming in 15 cm layers finishing top surface to the required level curing etc..etc..and complete for finished item of work. (APSS No. 402)	14.30	Cum		

S.No	Description of Item	Quantity	per	Rate	Amount
4.	Plain Cement Concrete (1:3:6) nominal mix using 20mm size graded machine crushed hard granite metal (coarse aggregate - as per IS 383 - 1970 and IS 2386 Part 1 to Part 8) from approved quarry using concrete Mixer 10 / 7 cft (0.2 / 0.8 cum) capacity including cost and conveyance of all materials like cement, fine aggregate(sand), coarse aggregate, water etc. to site including all charges for machine mixing, hire charges of concrete mixer, laying concrete in position, curing etc., & lift charges , and f for finished item of work. (APSS No. 402)	15.71	Cum		
5.	Conveyance of un-useful excavated earth to a distance of 2 KM for disposal including hire charges of T & P, labour charges etc., and overheads & contractors profit complete for finished item of work.	28.60	Cum		
6.	Supplying and fixing of Pre-painted Galvalume Trapezoidal Profile Roofing sheets with 0.50mm thickness. Coating: Alu-Zinc coating AZ150 GSM. Tensile Strength: 550 MPA. Paint coating: Regular Modified Polyester painting. Painting Thickness (Top): 18 to 20 Microns, (Bottom): 5 to 7 Microns. Sheet Width: 1.020, Length: Maximum 12 Meters with Regular Range Colours fixed with G.I 'J' bolts & nuts 8 mm dia with bitumen & G.I limpet washers filled with white lead & including a coat of approved steel primer and two coats of approved paint on over lapping of sheets complete (up to a pitch of 600) etc., complete, excluding the cost of purlins, rafters, trusses including cost and conveyance of all materials , labour charges , etc., complete for finished item of work in all floors.	158.11	Sqm		
7.	Supply and fixing of Ms pipe 76mm dia 3.2mm thick support for truss including base plate including cost of all materials labour charges fabrication charges fixing charges complete for finished item of work	66.00	Rmt		
8.	Supply and fixing of truss using Ms box section 40x40x2.6mm as principal rafter, common rafter, and Ties as per drawing including cost of all materials labour charges fabrication charges fixing charges complete for finished item of work as per drawings	55.00	Rmt		
9.	Supply and fixing of purlins using Ms box section 40x40x2.6mm including cost of all materials labour charges fabrication charges fixing charges complete for finished item of work	162.00	Rmt		

S.No	Description of Item	Quantity	per	Rate	Amount
10.	Painting two coats with synthetic enamel paint Grade-II VOC (Volatile Organic Compound) content less than 50 grams/litre over primer coat of red oxide to new iron work including cost and conveyance of all materials to site, incidental, operational and all labour charges etc., and complete for finished item of work in all floors. (SS No. 1201, 1212 & 1207).	58.37	Sqm		
Total					
Extra GST @12%					
Grand Total of Rs.					

Further, the contractors/firms are requested to mention the GST Number in quotation otherwise the quotation stands cancelled.

The Registrar, Yogi Vemana University reserves the right to accept/reject/cancel any or all the quotations without assigning any reason thereof.


REGISTRAR
YOGI VEMANA UNIVERSITY
KADAPA-516003.

To

Copy to Web Committee, Yogi Vemana University, Kadapa with request to place the call letter in University web site.

Copy to the Notice Board

Copy to file