

**యోగి వేమన విశ్వవిద్యాలయం**  
**YOGI VEMANA UNIVERSITY**  
 Vemanapuram, Kadapa - 516003, Andhra Pradesh, INDIA.  
 (తన్నుతానెరిగిన తానెపో బ్రహ్మంబు :: If know thyself, Thou Art the Divinity)

ఆచార్య కె. చంద్రయ్య, M.Sc., M.Phil., Ph.D.,  
 కులసచివులు

Prof. K. Chandraiah, M.Sc., M.Phil., Ph.D.,  
 REGISTRAR



08562 -225429  
 Fax : 08562 -225419  
 98858 07919  
 94900 83127  
 ✉ registryvu@gmail.com  
 chandraiah2002@yahoo.co.uk  
 kchandraiah@svuniversity.ac.in

No.YVU/ Engg.Dept/UE/JTO/Paving with precast concrete blocks for North side of  
 Canteen/web Quotation/2018-19 Dt. 27-02-2019

From  
 The Registrar  
 Yogi Vemana University  
 Kadapa

**Sub:-** Y.V.U- Engineering Section –Engineering Department- **Construction of paving with precast concrete blocks for north side of Canteen in Y.V. University, Kadapa (in view of Urgency)**– Permission to call for the quotations thorough University Web site - Request - Reg.

**Ref:-** Orders of the Hon'ble Vice Chancellor dated : 27-02-2019

-o0o-

The eligible Contractors are requested to send their lowest quotation towards **“Construction of paving with precast concrete blocks for north side of Canteen in Y.V.University, Kadapa (in view of Urgency)”** the quotation should be addressed to the Registrar, Yogi Vemana University, Kadapa to reach this office on or before 02-03-2019.

| S.No | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Quantity | per | Rate | Amount |
|------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----|------|--------|
| 1.   | Earth work excavation for foundations (Manual Means) of buildings, septic tank, sump, compound wall in ordinary soils and depositing on bank with an initial lead of 10m and depth up to 3m including all operational, incidental, labour charges such as shoring, sheeting, planking, strutting etc., and complete for finished item of work excluding dewatering charges etc., as per SS 20 B (APSS 308)                                                                           | 26.40    | Cum |      |        |
| 2.   | Filling with carted coarse sand in trenches, sides of foundations and basement with initial lead in layers not exceeding 15cm thick, watering and ramming including cost and conveyance of water to work site and all operational .incidental .labour charges, hire charges of T&P etc., and complete for finished item of work(APSS NO.309&310)                                                                                                                                     | 19.80    | Cum |      |        |
| 3.   | Masonry work in CM(1:6) prop (Cement : Sand) in superstructure with fly ash cement / lime solid blocks of size 290mm x 225mm x 140mm from approved source having minimum crushing strength of 50 Kg/Sqcm. including cost and conveyance of all materials like cement, sand, bricks, water etc., to site, labour charges, like mixing cement mortar, scaffolding charges, constructing masonry, lift charges, curing, etc., complete for finished item of work. (APSS No. 501 & 504). | 1.90     | Cum |      |        |



| S.No                      | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Quantity | per | Rate | Amount |
|---------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----|------|--------|
| 4.                        | Plastering 12mm thick single coat in CM(1:5) using screened sand including cost and conveyance of all materials like cement, sand, water etc., to site and all operational, incidental charges on materials and including cost of all labour charges for mixing mortar, finishing, curing as directed by Engineer-in-charge etc., and complete for finished item of work.(SS 901,903 & 904)                                                                                                                 | 21.45    | Sqm |      |        |
| 5.                        | PCC (1:5:10) proportion nominal mix using 20mm size graded machine crushed HBG chips from approved quarry including cost and conveyance of all materials like cement, sand, coarse aggregate, water, etc. to site, including seignorage charges, sales and other taxes on all materials and including all charges for hand mixing, laying concrete in foundations, ramming in 15cm layers, finishing top surface to the required level, curing, etc. complete for the finished item of work as per APSS 402 | 18.80    | Sqm |      |        |
| 6.                        | Supply of precast concrete blocks for paving of M-30 grade and thickness not less than 50 mm for Non-traffic areas conforming to IS 15658:2006 in all shapes and designs as per the manufacturer's etc., Complete for finished item of work.                                                                                                                                                                                                                                                                | 179.53   | Sqm |      |        |
| 7.                        | Labour charges for laying & fixing of precast concrete blocks for paving of all grades, any thickness, all sizes & shapes including all labour charges for loading & unloading, laying to desired lines and levels complete excluding cost of cement, sand, water, electricity etc complete for finished item of work.                                                                                                                                                                                      | 179.53   | Sqm |      |        |
| <b>Total</b>              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |          |     |      |        |
| <b>Add GST @12%</b>       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |          |     |      |        |
| <b>Grand Total of Rs.</b> |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |          |     |      |        |

Further, the contractors are requested to mention the GST Number in quotation otherwise the quotation stands cancelled.

The Registrar, Yogi Vemana University reserves the right to accept/reject/cancel any or all the quotations without assigning any reason thereof.

  
**REGISTRAR**  
**YOGI VEMANA UNIVERSITY**  
**KADAPA-516003.**

**To**

Copy to Web Committee, Yogi Vemana University, Kadapa with request to place the call letter in University web site.

Copy to the Notice Board

Copy to file