

యోగి వేమన విశ్వవిద్యాలయం
YOGI VEMANA UNIVERSITY

Vemanapuram, Kadapa - 516003, Andhra Pradesh, INDIA.
(తన్నుతానెరిగిన తానెపో బ్రహ్మంబు :: If know thyself, Thou Art the Divinity)

ఆచార్య కె. చంద్రయ్య, M.Sc., M.Phil., Ph.D.,

కులసచివులు

Prof. K. Chandraiah, M.Sc., M.Phil., Ph.D.,

REGISTRAR



08562 -225429

Fax : 08562 -225419

98858 07919

94900 83127

registraryvu@gmail.com
chandraiah2002@yahoo.co.uk
kchandraiah@svuniversity.ac.in

No.YVU/ Engg.Dept/UE/JTO/Extension roofing sheet north side of Canteen(In view of Convocation Programme)/web Quotation/2018-19 Dt. 15-02-2019

From

The Registrar

Yogi Vemana University

Kadapa

Sub:- Y.V.U- Engineering Section –Engineering Department- **Extension of Galvalume Trapezoidal roofing sheet north side of Canteen (in view of convocation programme) at Yogi Vemana University Campus, Kadapa –** Permission to call for the quotations thorough University Web site - Request - Reg.

Ref:- Orders of the Hon'ble Vice Chancellor dated : 15-02-2019

-o0o-

The eligible Contractors are requested to send their lowest quotation towards **“Extension of Galvalume Trapezoidal roofing sheet north side of Canteen (in view of convocation programme) at Yogi Vemana University Campus, Kadapa”** the quotation should be addressed to the Registrar, Yogi Vemana University, Kadapa to reach this office on or before 18-02-2019.

S.No	Description of Item	Quantity	per	Rate	Amount
1.	Earth work excavation for foundations (Manual Means) of buildings, septic tank, sump, compound wall in ordinary soils and depositing on bank with an initial lead of 10m and depth up to 3m including all operational, incidental, labour charges such as shoring, sheeting, planking, strutting etc., and complete for finished item of work excluding dewatering charges etc., as per SS 20 B(APSS 308)	0.50	Cum		
2.	Plain Cement Concrete (1:3:6) nominal mix using 20mm size graded machine crushed hard granite metal (coarse aggregate - as per IS 383 - 1970 and IS 2386 Part 1 to Part 8) from approved quarry using concrete Mixer 10 / 7 cft (0.2 / 0.8 cum) capacity including cost and conveyance of all materials like cement, fine aggregate(sand), coarse aggregate, water etc. to site including all charges for machine mixing, hire charges of concrete mixer, laying concrete in position, curing etc., & lift charges , and f for finished item of work. (APSS No. 402)	0.60	Cum		
3.	Painting two coats with synthetic enamel paint Grade-II VOC (Volatile Organic Compound) content less than 50 grams/litre over primer coat of red oxide to new iron work including cost and conveyance of all materials to site, incidental, operational and all labour charges etc., and overheads & contractors profit complete for finished item of work in all floors. (SS No. 1201, 1212 & 1207).	16.00	Sqm		

S.No	Description of Item	Quantity	per	Rate	Amount
4.	Supplying and fixing of Pre-painted Galvalume Trapezoidal Profile Roofing sheets with 0.50mm thickness, Coating: Alu-Zinc coating AZ150 GSM. Tensile Strength: 550 MPA. Paint coating: Regular Modified Polyester painting. Painting Thickness (Top): 18 to 20 Microns, (Bottom): 5 to 7 Microns. Sheet Width: 1.020, Length: Maximum 12 Meters with Regular Range Colours fixed with G.I 'J' bolts & nuts 8 mm dia with bitumen & G.I limpet washers filled with white lead & including a coat of approved steel primer and two coats of approved paint on over lapping of sheets complete (up to a pitch of 600) etc., complete, excluding the cost of purlins, rafters, trusses including cost and conveyance of all materials , labour charges , etc., complete for finished item of work in all floors.	44.00	Sqm		
5.	Supply and fabricating fitting and fixing of MS Trusses using MS square hollow section of 72X72X3.2 mm as Support poles is 3.65 m @04 Nos are using vertical support to truss as MS Square hollow section of 50X50X2.6mm purlins is 11.90 m @04 Nos long and MS Rectangular hollow section of 80x40x2.6mm thick rafters is 3.00 m @04 Nos including cost of all materials labour charges fabrication charges fixing charges complete as per drawings and design and in the direction of Engineer in charge all complete.	1.00	Unit		
Total					
Extra GST @12%					
Grand Total of Rs.					

Further, the contractors are requested to mention the GST Number in quotation otherwise the quotation stands cancelled.

The Registrar, Yogi Vemana University reserves the right to accept/reject/cancel any or all the quotations without assigning any reason thereof.


REGISTRAR
YOGI VEMANA UNIVERSITY
KADAPA-516003.

To

Copy to Web Committee, Yogi Vemana University, Kadapa with request to place the call letter in University web site.

Copy to the Notice Board

Copy to file