

**Sub:** Yogi Vemana University Campus, Kadapa – Fabrication, supply, transportation and erection of 8 Meters M.S swaged poles for the University Road dividers and other places in YVU Campus, Kadapa – Sealed quotations called for - From firms/suppliers - Reg.

**Ref:** Orders of the Vice-Chancellor dated 16-02-2016.

@@@

The following are the specifications for various items:

Sl. No.	Description of item	Unit	Quantity	Rate Rs. (Approximate)	Amount Rs.
1	Fabrication, supply, transportation and erection of 8 meters MS swaged poles of uniform height of 25 to 26 feet up to site, The pole should be painted with primary coat of red oxide and 2nd coat of silver paint and black bituminous paint up to ground level with base rods or strips and the fitting pipe bracket supplied by the University should be welded to the pole at the top, including excavation of pit and concrete upto ground level with cost of all materials etc., complete including all taxes as per following specifications.	Each	20		
	Length of the Pole : 8 Mtrs.	Bottom :20 ft	Top :6 ft		
		Outer dia / Thickness	Outer dia / Thickness		
		7.62 cm/ 3.5 mm	6.35 cm/ 3.5 mm		

The following Terms & conditions apply:

- 1) Firm has to furnish Authorized dealership Certificate along with the quotation wherever applicable.
- 2) Firm has to furnish copies of work orders/Purchase Orders recently executed.
- 3) Least quoted Firm receiving the Work Order should execute the work within 7 days from the date of issue of Work Order.

Sealed quotations may be sent by **Registered Post/Speed Post/Courier services or parties can visit University and deposit the sealed quotations in the Drop Box available at Registrar's office** super scribed as '**Quotations for the Fabrication, supply, transportation and erection of 8 Meters M.S swaged poles for the University Road dividers and other places in YVU Campus, Kadapa should reach The Registrar, Yogi Vemana University, Kadapa, Andhra Pradesh, Pin: 516003, on or before 23<sup>rd</sup> February 2016 by 4:00 p.m.** The University is not responsible for the postal delays.

  
 16/2/16  
**REGISTRARi/c**