

**యోగి వేమన విశ్వవిద్యాలయం**  
**YOGI VEMANA UNIVERSITY**

Vemanapuram, Kadapa - 516003, Andhra Pradesh, INDIA.  
(తన్నుతానెరిగిన తానెవో బ్రహ్మంబు :: If know thyself, Thou Art the Divinity)

ఆచార్య కె. చంద్రయ్య, M.Sc., M.Phil., Ph.D.,  
కులసచివులు  
Prof. K. Chandraiah, M.Sc., M.Phil., Ph.D.,  
REGISTRAR



08562 -225429  
Fax : 08562 -225419  
98858 07919  
94900 83127  
registraryvu@gmail.com  
chandraiah2002@yahoo.co.uk  
kchandraiah@svuniversity.ac.in

No.YVU/ Engg.Dept/UE/JTO/Painting and Maintenance to Canteen at YVU Campus/web  
Quotation/2018-19 Dt. 27-02-2019

**From**  
**The Registrar**  
Yogi Vemana University  
Kadapa

**Sub:-** Y.V.U- Engineering Section –Engineering Department- **Providing painting and Maintenance to Canteen at YVU Campus, Kadapa (in view of Urgency)**–  
Permission to call for the quotations thorough University Web site - Request -  
Reg.

**Ref:-** Orders of the Hon`ble Vice Chancellor dated : 27-02-2019

-o0o-

The eligible Contractors are requested to send their lowest quotation towards **“Providing painting and Maintenance to Canteen at YVU Campus, Kadapa (in view of Urgency)”** the quotation should be addressed to the Registrar, Yogi Vemana University, Kadapa to reach this office on or before 02-03-2019.

S.No	Description of Item	Quantity	per	Rate	Amount
1.	Plain Cement Concrete (1:2:4) using 20mm size graded machine crushed hard granite metal (coarse aggregate - as per IS 383 - 1970 and IS 2386 Part 1 to Part 8) from approved quarry using concrete Mixer 10 / 7 cft (0.2 / 0.8 cum) capacity including cost and conveyance of all materials like cement, fine aggregate(sand), coarse aggregate, water etc. to site including all charges for machine mixing, hire charges of concrete mixer, laying concrete in position, curing etc., & lift charges , and for septic tank bed, in sunken slabs for finished item of work. (APSS No. 402)	0.06	Cum		
2.	Reinforced Brick Masonry for partition walls (11.0 cm thick) in CM (1:4) prop. (Cement : Sand) using common burnt clay bricks of class as per Table- I of IS:1077-1992, Non- Modular or traditional size 23 x 11 x 7 cms from approved source having minimum crushing strength of 40 Kg/Sq.cm and placing 2 Nos. of 6mm M.S plain rods in every third layer with free ends of the reinforcement pegged into mortar joints of main brick walls where applicable including cost and conveyance of all materials like cement, steel, sand, bricks, water etc., to site, all operational, incidental charges such as labour charges for mixing cement mortar, scaffolding charges, constructing masonry, lift charges, curing, etc., and but excluding cost of steel and its fabrication charges complete for finished item of work. (APSS No. of 501 & 509)	2.94	Sqm		



S.No	Description of Item	Quantity	per	Rate	Amount
3.	Plastering 12mm thick single coat in CM(1:5) using screened sand including cost and conveyance of all materials like cement, sand, water etc., to site and all operational, incidental charges on materials and including cost of all labour charges for mixing mortar, finishing, curing as directed by Engineer-in-charge etc., and complete for finished item of work.(SS 901,903 & 904)	11.20	Sqm		
4.	Providing dadoing to walls with glazed red or white full body ceramic wall tiles of size 200 x 300 mm / 245 mm x 325 mm and thickness 6 mm 1st quality conforming to IS:13711, IS:13712, IS:13630 (Parts 1 to 15) of any colour and finish in all shades and designs with borders as approved by Engineer-in-Charge set over base coat of CM(1:5) 12 mm thick using screened sand with cement slurry of honey like consistency spread at the rate of 3.30 kgs per sqm and jointing with white cement paste mixed with pigment of matching shade to full depth, including cost of all materials like tiles, cement, sand and water etc., and complete for finished item of work.	10.45	Sqm		
5.	Supply & application of one coat water based cement primer of interior grade I and two coats of acrylic emulsion paint having VOC (Volatile Organic Compound) content less than 50 grams/litre for internal walls including cost and conveyance of all materials to site, incidental, operational and all labour charges etc., and complete for finished item of work in all floors.	286.76	Sqm		
6.	Supply & application of one coat water based cement primer of exterior grade II and two coats of acrylic exterior emulsion paint having VOC (Volatile Organic Compound) content less than 50 grams/litre for exterior walls including cost and conveyance of all materials to site, incidental, operational and all labour charges etc., and complete for finished item of work in all floors.	328	Sqm		
7.	Supply and fixing of Ashirvad/ Ajay/ Astral Flowguard or equivalent CPVC Pipes and Fittings SDR 13.5 to meet the requirement of ASTM-D 2846 and are produced in CTS (Copper Tube Sizes 1/2" to 2") for hot and cold water (IS 15778:2007) including cost and conveyance of all materials to site, labour charges for fixing, overheads & contractors profit complete for finished item of work at all floor levels.	15	Rmt		



S.No	Description of Item	Quantity	per	Rate	Amount
8.	Supplying and fixing NP bib taps of size 12.70mm dia of Indian make heavy duty (short body) as approved by the Engineer-In-Charge including cost and conveyance of all materials, labour charges , complete for finished item of work in all floors.	7.00	Nos		
9.	Supplying and fixing of 4" (101.6mm) multi floor trap with jali - UPVC/SWR pipe fittings as per site requirements with standard practice for all floors including cost and conveyance of all materials to site, labour charges , etc., complete for finished item of work.	2.00	Nos		
10.	Supplying and fixing of SWR PVC pipes (as per ISI standards) 4 Kg/Sq.cm. for using 110 mm dia and fixing all special such as plain bends, off sets, door bends, single junctions, double junctions as per site requirement, fixing with PVC clamps if necessary with required number of Bombay nails including cost and conveyance of all materials to site, labour charges etc.complete for finished item of work at all floor levels. (APSS No. 1302 1319 & 1326)	18.00	Rmt		
11.	Providing and fixing Thermocole False ceiling in true horizontal level 600mm x 600mm using 12mm thick Thermocole sheet, including cost and conveyance of all materials and labour charges such as cutting , fixing of standing of frame work exposing roof complete for finished item of work in all floors.	96.33	Sqm		
12.	Supply and fixing of LED Slim Panel Round /Square suitable for Recessed / Surface mounting made of die cast aluminum body with powder coating, acrylic diffuser with Driver as per IS: 15885 (Part 2/ Sec 13) : 2012 , operating voltaGE-Venture ranGE-Venture of 150 to 265 Volts AC, P.F > 0.9, SurGE-Venture protection: 2KV, THD<10%, with high power LED's having efficacy of > 120 lumins/watt,CCT: 3000K - 5700K, minimum CRI>70, .etc., complete a) LUMINAIRE MAKE : Phillips /Lighting Technologies(LT) / GE-Venture / Crompton / Wipro / Bajaj / Havells /Halonix/Jaquar/HPL b) LED MAKE : PHILIPS LUMILEDS / CREE / NICHIA / OSRAM / SAMSUNG.	6.00	Nos		
<b>Total of Rs.</b>					
<b>Add GST @12%</b>					
<b>Grand Total of Rs.</b>					

Further, the contractors are requested to mention the GST Number in quotation otherwise the quotation stands cancelled.

The Registrar, Yogi Vemana University reserves the right to accept/reject/cancel any or all the quotations without assigning any reason thereof.

To

  
**REGISTRAR**  
**YOGI VEMANA UNIVERSITY**  
**KADAPA-516003.**

Copy to Web Committee, Yogi Vemana University, Kadapa with request to palce the call letter in University web site.

Copy to the Notice Board

Copy to file