

యోగి వేమన విశ్వవిద్యాలయం
YOGI VEMANA UNIVERSITY

Vemanapuram, Kadapa - 516003, Andhra Pradesh, INDIA.
(తన్నుతానెరిగిన తానెపో బ్రహ్మంబు :: If know thyself, Thou Art the Divinity)

ఆచార్య కె. చంద్రయ్య, M.Sc., M.Phil., Ph.D.,
కులసచివులు

Prof. K. Chandraiah, M.Sc., M.Phil., Ph.D.,
REGISTRAR



☎ 08562 -225429
Fax : 08562 -225419
98858 07919
94900 83127

✉ registryvu@gmail.com
chandraiah2002@yahoo.co.uk
kchandraiah@svuniversity.ac.in

No. YVU/ Engg.Dept/UE/JTO/Galvalume Trapezoidal profile roofing sheets washing
platforms at Ladies Hostels(In view of Convocation Programme)/web Quotation/2018-19

Dt. 15-02-2019

From

The Registrar

Yogi Vemana University
Kadapa

Sub:- Y.V.U- Engineering Section –Engineering Department- **Providing Galvalume Trapezoidal profile roofing sheets over washing platforms at Chitravathi Ladies Hostels (In View of Convocation Programme) at University Campus, Yogi Vemana University, Kadapa** – Permission to call for the quotations through University Web site - Request - Reg.

Ref:- Orders of the Hon'ble Vice Chancellor dated : 15-02-2019

-o0o-

The eligible Contractors are requested to send their lowest quotation towards **“Providing Galvalume Trapezoidal profile roofing sheets over washing platforms at Chitravathi Ladies Hostels (In View of Convocation Programme) at University Campus, Yogi Vemana University, Kadapa”** the quotation should be addressed to the Registrar, Yogi Vemana University, Kadapa to reach this office on or before 18-02-2019.

S.No	Description of Item	Quantity	per	Rate	Amount
1.	Earth work excavation for foundations (Manual Means) of buildings, septic tank, sump, compound wall in ordinary soils and depositing on bank with an initial lead of 10m and depth up to 3m including all operational, incidental, labour charges such as shoring, sheeting, planking, strutting etc., and complete for finished item of work excluding dewatering charges etc., as per SS 20 B(APSS 308)	1.00	Cum		
2.	Plain Cement Concrete (1:3:6) nominal mix using 20mm size graded machine crushed hard granite metal (coarse aggregate - as per IS 383 - 1970 and IS 2386 Part 1 to Part 8) from approved quarry using concrete Mixer 10 / 7 cft (0.2 / 0.8 cum) capacity including cost and conveyance of all materials like cement, fine aggregate(sand), coarse aggregate, water etc. to site including all charges for machine mixing, hire charges of concrete mixer, laying concrete in position, curing etc., & lift charges , and f for finished item of work. (APSS No. 402)	1.20	Cum		

-192-

S.No	Description of Item	Quantity	per	Rate	Amount
3.	Supplying fabricating, fitting and fixing steel tubular trusses of size 100X50X3.0 mm MS Rectagular Hallow Section @3.2 m @04 Nos & 2.9 M @04 Nos, 80X40X3.0 mm MS Rectagular Hallow Section @3.1 m @04 Nos, 60X40 X2.5 mm MS Rectangular Hallow Section of lenth 13.75 m @04 Nos and L angles of Size 40 X40X3 mm of 0.3 m @16 Nos including cutting hoisting fixing in position and applying a priming coat of approved steel primer welded and bolted including specials shape washer etc as per the standard specification and design and direction of Engineer in charge all complete	1.00	Nos		
4.	Painting two coats with synthetic enamel paint Grade-II VOC (Volatile Organic Compound) content less than 50 grams/litre over primer coat of red oxide to new iron work including cost and conveyance of all materials to site, incidental, operational and all labour charges etc., and overheads & contractors profit complete for finished item of work in all floors. (SS No. 1201, 1212 & 1207).	24.00	Sqm		
5.	Supplying and fixing of Pre-painted Galvalume Trapezoidal Profile Roofing sheets with 0.50mm thickness. Coating: Alu-Zinc coating AZ150 GSM. Tensile Strength: 550 MPA. Paint coating: Regular Modified Polyester painting. Painting Thickness (Top): 18 to 20 Microns, (Bottom): 5 to 7 Microns. Sheet Width: 1.020, Length: Maximum 12 Meters with Regular Range Colours fixed with G.I 'J' bolts & nuts 8 mm dia with bitumen & G.I limpet washers filled with white lead & including a coat of approved steel primer and two coats of approved paint on over lapping of sheets complete (up to a pitch of 600) etc., complete, excluding the cost of purlins, rafters, trusses including cost and conveyance of all materials , labour charges , overheads and contractors profit etc., complete for finished item of work in all floors.	50.90	Sqm		
				Total	
				Extra GST @12%	
				Grand Total of Rs.	

Further, the contractors are requested to mention the GST Number in quotation otherwise the quotation stands cancelled.

The Registrar, Yogi Vemana University reserves the right to accept/reject/cancel any or all the quotations without assigning any reason thereof.

To

Copy to Web Committee, Yogi Vemana University, Kadapa with request to palce the call letter in University web site.

Copy to the Notice Board

Copy to file


REGISTRAR
YOGI VEMANA UNIVERSITY

KADAPA-516003.