

**యోగి వేమన విశ్వవిద్యాలయం**  
**YOGI VEMANA UNIVERSITY**  
 Vemanapuram, Kadapa - 516003, Andhra Pradesh, INDIA.  
 (తన్నుతానెరిగిన తానెపో బ్రహ్మంబు :: If know thyself, Thou Art the Divinity)

ఆచార్య కె. చంద్రయ్య, M.Sc., M.Phil., Ph.D.,  
 కులసచివులు  
 Prof. K. Chandraiah, M.Sc., M.Phil., Ph.D.,  
 REGISTRAR



08562 -225429  
 Fax : 08562 -225419  
 98858 07919  
 94900 83127  
 registrarvu@gmail.com  
 chandraiah2002@yahoo.co.uk  
 kchandraiah@svuniversity.ac.in

No.YVU/ Engg.Dept/UE/JTO/Scooter parking shed at Sir C.V.Raman Science Building/web Quotation/2018-19 Dt. 25-02-2019

**From**  
**The Registrar**  
 Yogi Vemana University  
 Kadapa

**Sub:-** Y.V.U- Engineering Section –Engineering Department- **Construction of Scooter Parking sheds near Sir C.V.Raman Science building in Yogi Vemana University, Kadapa** – Permission to call for the quotations through University Web site - Request - Reg.

**Ref:-** Orders of the Hon'ble Vice Chancellor dated : 25-02-2019

-o0o-

The eligible Contractors/firms are requested to send their lowest quotation towards **“Construction of Scooter Parking sheds near Sir C.V.Raman Science building in Yogi Vemana University, Kadapa”** the quotation should be addressed to the Registrar, Yogi Vemana University, Kadapa to reach this office on or before 28-02-2019.

S.No	Description of Item	Quantity	per	Rate	Amount
1.	Earth work excavation for foundations (Manual Means) of buildings, septic tank, sump, compound wall in ordinary soils and depositing on bank with an initial lead of 10m and depth up to 3m including all operational, incidental, labour charges such as shoring, sheeting, planking, strutting etc., and complete for finished item of work excluding dewatering charges etc., as per SS 20 B(APSS 308)	0.55	Cum		
2.	Filling with carted gravel in trenches, sides of foundations and basement with initial lead in layers not exceeding 15cm thick, watering and ramming including cost and conveyance of water to work site and all operational, incidental, labour charges, hire charges of T&P etc., and complete for finished item of work(APSS NO.309&310)	17.20	Cum		
3.	Plain Cement Concrete (1:5:10) (cement: fine aggregate: Coarse aggregate) for foundations and under flooring bed using coarse aggregate 40mm size hard, machine crushed granite from approved quarry including cost and conveyance of all materials like cement, sand, coarse aggregate, water etc. to site, sales & other taxes on all materials and including all charges for machine mixing, laying concrete in foundations and under flooring bed, ramming in 15 cm layers finishing top surface to the required level curing etc.,and complete for finished item of work. (APSS No. 402)	15.20	Cum		
4.	Vibrated Plain Cement Concrete (1:3:6) nominal mix using 40mm size machine crushed hard granite metal and 20mm graded machine crushed hard granite metal (coarse aggregate) in (2:1) ratio from approved quarry using concrete Mixer 10 / 7 cft (0.2 / 0.8 cum) capacity including cost and conveyance of all materials like cement, fine aggregate (sand), coarse aggregate, water etc. to site, all charges for mixing and hire charges of concrete mixer, laying concrete in position, vibrating, curing, centering charges, etc.,for finished item of work for flooring	15.60	Cum		

S.No	Description of Item	Quantity	per	Rate	Amount
5.	Supply and fixing of MS Hollow Square pipes 100x100x5.00mm using Vertical poles, fixing of top and bottom Ms plates of size (0.23*0.23*12mm thick ) 2Nos, and fish plates 8Nos ( 1/2*0.30*0.15 size ) using 12mm thick Ms plate in supported to pole ,including cost and conveyance of all material labor charges fabrication and fixing charges complete for finished item of work	24.00	Rmt		
6.	Supply and fixing of Vertical MS iron Purlins of size of using 80mm x40mmx3.20 mm thick outer square frame ,including cost and conveyance of all material labor charges fabrication and fixing charges complete for finished item of work	217.00	Rmt		
7.	Supply and fixing of MS iron Trusses (TrangleShape) of size 5.50 x (0.15+0.45+0.15) m using 40x40x 3.20 mm thick MS Hollow Square pipe outer frame , verticals is 40x40x3.20mm thick Square pipe and cross lengths is 25x25x3.20mm thick Square pipe of Trusses including cost and conveyance of all material labor charges fabrication and fixing charges complete for finished item of work	10.00	Nos		
8.	Supplying and fixing of Pre-painted Galvalume Trapezoidal Profile Roofing sheets with 0.50mm thickness, Coating: Alu-Zinc coating AZ150 GSM. Tensile Strength: 550 MPA. Paint coating: Regular Modified Polyester painting. Painting Thickness (Top): 18 to 20 Microns, (Bottom): 5 to 7 Microns. Sheet Width: 1.020, Length: Maximum 12 Meters with Regular Range Colours fixed with G.I 'J' bolts & nuts 8 mm dia with bitumen & G.I limpet washers filled with white lead & including a coat of approved steel primer and two coats of approved paint on over lapping of sheets complete (up to a pitch of 600) etc., complete, excluding the cost of purlins, rafters, trusses including cost and conveyance of all materials , labour charges , etc., complete for finished item of work in all floors.	170.00	Sqm		
9.	Painting two coats with synthetic enamel paint Grade-II VOC (Volatile Organic Compound) content less than 50 grams/litre over primer coat of red oxide to new iron work including cost and conveyance of all materials to site, incidental, operational and all labour charges etc., and complete for finished item of work in all floors. (SS No. 1201, 1212 & 1207).	62.00	Sqm		
				Total	
				Extra GST @12%	
				<b>Grand Total of Rs.</b>	

Further, the contractors/firms are requested to mention the GST Number in quotation otherwise the quotation stands cancelled.

The Registrar, Yogi Vemana University reserves the right to accept/reject/cancel any or all the quotations without assigning any reason thereof.

  
**REGISTRAR**  
**YOGI VEMANA UNIVERSITY**  
**KADAPA-516003.**

To

Copy to Web Committee, Yogi Vemana University, Kadapa with request to palce the call letter in University web site.

Copy to the Notice Board

Copy to file