

యోగి వేమన విశ్వవిద్యాలయం
YOGI VEMANA UNIVERSITY

Vemanapuram, Kadapa - 516003, Andhra Pradesh, INDIA.
(తన్ను అనెరిగిన అనెపో బ్రహ్మంబు :: If know thyself, Thou Art the Divinity)

ఆచార్య కె. చంద్రయ్య, M.Sc., M.Phil., Ph.D.,

కులసచివులు

Prof. K. Chandraiah, M.Sc., M.Phil., Ph.D.,

REGISTRAR



08562 -225429

Fax : 08562 -225419

98858 07919

94900 83127

registraryvu@gmail.com
chandraiah2002@yahoo.co.uk
kchandraiah@svuniversity.ac.in

No.YVU/ Engg.Dept/UE/JTO/Shifting of Generator shed at Arts & Commerce
Building/web Quotation/2018-19 Dt. 25-02-2019

From

The Registrar

Yogi Vemana University

Kadapa

Sub:- Y.V.U- Engineering Section –Engineering Department- **Shifting of Generator & Construction of Shelter for Generator at New Arts & Commerce Building in Yogi Vemana University, Kadapa** – Permission to call for the quotations thorough University Web site - Request - Reg.

Ref:- Orders of the Hon'ble Vice Chancellor dated : 25-02-2019

-o0o-

The eligible Contractors/firms are requested to send their lowest quotation towards **“Shifting of Generator & Construction of Shelter for Generator at New Arts & Commerce Building in Yogi Vemana University, Kadapa”** the quotation should be addressed to the Registrar, Yogi Vemana University, Kadapa to reach this office on or before 28-02-2019.

S.No	Description of Item	Quantity	per	Rate	Amount
1.	Earth work excavation for foundations (Mechanical Means) for buildings in ordinary soils and depositing on bank for all lifts and with an initial lead of 10m and 3m to 6m depth including all operational, incidental, labour charges such as shoring, sheeting, planking, strutting etc., and complete for finished item of work excluding dewatering charges etc., as per SS 20 B(APSS 308)	2.66	Cum		
2.	Plain Cement Concrete (1:5:10) (cement: fine aggregate: Coarse aggregate) for foundations and under flooring bed using coarse aggregate 40mm size hard , machine crushed granite from approved quarry including cost and conveyance of all materials like cement, sand, coarse aggregate, water etc. to site, sales & other taxes on all materials and including all charges for machine mixing, laying concrete in foundations and under flooring bed, ramming in 15 cm layers finishing top surface to the required level curing etc.,etc.,and complete for finished item of work. (APSS No. 402)	0.67	Cum		
3.	Plain Cement Concrete (1:3:6) nominal mix using 20mm size graded machine crushed hard granite metal (coarse aggregate - as per IS 383 - 1970 and IS 2386 Part 1 to Part 8) from approved quarry using concrete Mixer 10 / 7 cft (0.2 / 0.8 cum) capacity including cost and conveyance of all materials like cement, fine aggregate(sand), coarse aggregate, water etc. to site including all charges for machine mixing, hire charges of concrete mixer, laying concrete in position, curing etc., & lift charges , and f for finished item of work. (APSS No. 402)	4.48	Cum		

S.No	Description of Item	Quantity	per	Rate	Amount
4.	Supplying and fixing of Pre-painted Galvalume Trapezoidal Profile Roofing sheets with 0.50mm thickness, Coating: Alu-Zinc coating AZ150 GSM. Tensile Strength: 550 MPA. Paint coating: Regular Modified Polyester painting. Painting Thickness (Top): 18 to 20 Microns, (Bottom): 5 to 7 Microns. Sheet Width: 1.020, Length: Maximum 12 Meters with Regular Range Colours fixed with G.I 'J' bolts & nuts 8 mm dia with bitumen & G.I limpet washers filled with white lead & including a coat of approved steel primer and two coats of approved paint on over lapping of sheets complete (up to a pitch of 600) etc., complete, excluding the cost of purlins, rafters, trusses including cost and conveyance of all materials, labour charges, etc., complete for finished item of work in all floors.	15.00	Sqm		
5.	Supply and fabricating fitting and fixing of MS Trusses using MS square hollow section of 40x40x2.6mm as truss, using vertical support to truss as MS round hollow section of 75x3.2mm outer dia and purlins as MS Rectangle hollow section of 60x40x2.6mm thick and with base plates including cost of all materials labour charges fabrication charges fixing charges complete as per drawings and design and in the direction of Engineer in charge all complete. (4.5mx3m)	1.00	Unit		
6.	Painting two coats with synthetic enamel paint Grade-II VOC (Volatile Organic Compound) content less than 50 grams/litre over primer coat of red oxide to new iron work including cost and conveyance of all materials to site, incidental, operational and all labour charges etc., and overheads & contractors profit complete for finished item of work in all floors. (SS No. 1201, 1212 & 1207).	6.67	Sqm		
7.	Plastering 12mm thick single coat in CM(1:5) using screened sand including cost and conveyance of all materials like cement, sand, water etc., to site and all operational, incidental charges on materials and including cost of all labour charges for mixing mortar, finishing, curing as directed by Engineer-in-charge etc., and overheads & contractors profit complete for finished item of work. (SS 901, 903 & 904)	13.25	Sqm		
8.	Providing Hydraulic truck crane 16t including cost of all labor desiel misc complete for finished item	2.50	Hrs		
				Total	
				Extra GST @12%	
				Grand Total of Rs.	

Further, the contractors/firms are requested to mention the GST Number in quotation otherwise the quotation stands cancelled.

The Registrar, Yogi Vemana University reserves the right to accept/reject/cancel any or all the quotations without assigning any reason thereof.

To

Copy to Web Committee, Yogi Vemana University, Kadapa with request to place the call letter in University web site.

Copy to the Notice Board


REGISTRAR
YOGI VEMANA UNIVERSITY
KADAPA-516003.