

యోగి వేమన విశ్వవిద్యాలయం
YOGI VEMANA UNIVERSITY
 Vemanapuram, Kadapa - 516003, Andhra Pradesh, INDIA.
 (తన్నుతానెరిగిన తానెవో బ్రహ్మయః :: If know thyself, Thou Art the Divinity)

అచార్య కె. చంద్రయ్య, M.Sc., M.Phil., Ph.D.,

కులసచివులు

Prof. K. Chandraiah, M.Sc., M.Phil., Ph.D.,

REGISTRAR



08562 -225429

Fax : 08562 -225419

98858 07919

94900 83127

registraryvu@gmail.com

chandraiah2002@yahoo.co.uk

kchandraiah@svuniversity.ac.in

No.YVU/ Engg.Dept/UE/JTO/Agar Bore well to YSR Engineering College Proddatur/web

Quotation/2018-19 Dt. 08-10-2018

From

The Registrar

Yogi Vemana University

Kadapa

Sub:- Y.V.U- Engineering Section –Engineering Department- **Providing Agar bore well for Y.S.R Engineering College of PRODDATUR, Y.S.R District** – Permission to call for the quotations thorough University Web site - Request - Reg.

Ref:- Orders of the Hon'ble Vice Chancellor dated : 08-10-2018

-o0o-

The eligible firms/Contractors are requested to send their lowest quotation towards **“Providing Agar bore well for Y.S.R Engineering College of PRODDATUR, Y.S.R District”** the quotation should be addressed to the Registrar, Yogi Vemana University, Kadapa to reach this office on or before 13-10-2018.

S.NO	DESCRIPTION OF ITEM	Qty	UNIT	RATE
1.	Drilling of Agar bore well by down the hole hammer (DTH) drilling to a finished dia of 250 mm (10") dia in all formations suitable for down the hole hammer drilling, hard rock formation all consolidated formation etc. and drilling in over burden to dia not less than 200 mm etc. including inserting of 180 mm dia PVC casing pipe, coupling caps any other relevant materials required up to the depth as directed by the department and conducting yield test including crew charges, cost of consumables, transportation charges of all other materials and all other charges required, assembling etc. complete all done to the satisfaction of the department but excluding cost of casing pipe, couplings and cap etc complete for finished item of work.	30.46 Rmt	1 Rmt	
2.	Supplying and fixing of SWR PVC pipes (Prince/Sudhakar/Kisan/Su preme or any ISI brand) 4 Kg/Sq.cm. and fixing all special such as plain bends, off sets, door bends, single junctions, double junctions as per site requirement, fixing with PVC clamps if necessary with required number of Bombay nails including cost and conveyance of all materials to site, labour charges, complete for finished item of work at all floor levels. (APSS No. 1302 1319 & 1326)	30.46 Rmt	1 Rmt	
3.	Providing slotting charges to 180 mm dia PVC casing pipe at Spacing as recommended by the Geologist Including all incidental charges, labour charges etc., complete for finished item of work.	30.46 Rmt	1 Rmt	
Total Amount of Rs. With including GST				


REGISTRAR

To

Copy to Web Committee, Yogi Vemana University, Kadapa with request to palce the call letter in University web site.

Copy to the Notice Board

Copy to file