

**యోగి వేమన విశ్వవిద్యాలయం**  
**YOGI VEMANA UNIVERSITY**

Vemanapuram, Kadapa - 516003, Andhra Pradesh, INDIA.  
(తన్నుతానెరిగిన తానెపో బ్రహ్మంబు :: If know thyself, Thou Art the Divinity)

ఆచార్య కె. చంద్రయ్య, M.Sc., M.Phil., Ph.D.,  
కులసచివులు

Prof. K. Chandraiah, M.Sc., M.Phil., Ph.D.,  
REGISTRAR



☎ 08562 -225429  
Fax : 08562 -225419  
98858 07919  
94900 83127

✉ registryvu@gmail.com  
chandraiah2002@yahoo.co.uk  
kchandraiah@svuniversity.ac.in

No.YVU/ Engg.Dept/UE/JTO/CC drain to Ladies Hostel/web Quotation/2018-19

Dt. 22-12-2018

**From**

**The Registrar**

Yogi Vemana University

Kadapa

**Sub:-** Y.V.U- Engineering Section –Engineering Department- **Construction of CC Drain at Chitravathi Ladies hostel of Yogi Vemana University, Kadapa**  
– Permission to call for the quotations thorough University Web site - Request - Reg.

**Ref:-** Orders of the Hon'ble Vice Chancellor dated : 22-12-2018

-o0o-

The eligible Contractors are requested to send their lowest quotation towards **“Construction of CC Drain at Chitravathi Ladies hostel of Yogi Vemana University, Kadapa”** the quotation should be addressed to the Registrar, Yogi Vemana University, Kadapa to reach this office on or before **02-01-2019**.

S.No	Description of Item	Quantity	per	Rate	Amount
1	Earth work excavation for foundations (Mechanical Means) for buildings in ordinary soils and depositing on bank for all lifts and with an initial lead of 10m and up to 3m depth including all operational, incidental, labour charges such as shoring, sheeting, planking, strutting etc., and complete for finished item of work excluding dewatering charges etc.	67.00	Cum		
2	Plain Cement Concrete (1:5:10) (cement: fine aggregate: Coarse aggregate) for foundations and under flooring bed using coarse aggregate 40mm size hard , machine crushed granite from approved quarry including cost and conveyance of all materials like cement, sand, coarse aggregate, water etc. to site, sales & other taxes on all materials and including all charges for machine mixing, laying concrete in foundations and under flooring bed, ramming in 15 cm layers finishing top surface to the required level curing etc., complete for finished item of work	18.50	Cum		

- 1 of 2 -

- 292 -

S.No	Description of Item	Quantity	per	Rate	Amount
3.	Vibrated Plain Cement Concrete (1:3:6) nominal mix using 20mm size machine crushed metal (coarse aggregate) from approved quarry including cost and conveyance of all materials like cement, fine aggregate (sand), coarse aggregate, water etc. to site, sales & other taxes on all materials, all charges for mixing, laying concrete in position, vibrating, curing, centering charges, etc., for finished item of work for footings and basement, Side walls.	17.50	Cum		
4.	Plastering 12mm thick single coat in CM(1:5) using screened sand including cost and conveyance of all materials like cement, sand, water etc., to site, including sales & other taxes on all materials, and all operational, incidental charges on materials and including cost of all labour charges for mixing mortar, finishing, curing as directed by Engineer-in-charge etc., complete for finished item of work	209.00	Sqm		
5.	Filling with useful available excavated earth (excluding rock) with a lead of 50 m in trenches, sides of foundations and basement with initial lead in layers not exceeding 15cm thick, watering and ramming including cost and conveyance of water to work site and all operational, incidental, labour charges, hire charges of T&P etc., and complete for finished item of work	12.50	Cum		
				Total	
				GST @12%	
				<b>Grand Total of Rs.</b>	

  
**REGISTRAR**  
**YOGI VEMANA UNIVERSITY**  
**KADAPA-516003.**

To

Copy to Web Committee, Yogi Vemana University, Kadapa with request to place the call letter in University web site.

Copy to the Notice Board

Copy to file