

**యోగి వేమన విశ్వవిద్యాలయం**  
**YOGI VEMANA UNIVERSITY**  
 Vemanapuram, Kadapa - 516003, Andhra Pradesh, INDIA.  
 (తన్నుతానెరిగిన తానెవో బ్రహ్మంబు :: If know thyself, Thou Art the Divinity)

11  
web

ఆచార్య కె. చంద్రయ్య, M.Sc., M.Phil., Ph.D.,  
 కులసచివులు

Prof. K. Chandraiah, M.Sc., M.Phil., Ph.D.,  
 REGISTRAR



08562-225429  
 Fax : 08562-225419  
 98858 07919  
 94900 83127  
 ✉ registryvu@gmail.com  
 chandraiah2002@yahoo.co.uk  
 kchandraiah@svuniversity.ac.in

No.YVU/ Engg.Dept/UE/JTO/New pipe line at old science block to cheyyeru sump (In view of  
 Cheif Minister Programme)/web Quotation/2018-19 Dt. 01-12-2018

**From**  
**The Registrar**  
 Yogi Vemana University  
 Kadapa

**Sub:-** Y.V.U- Engineering Section -Engineering Department- **Providing pipe line from additional source to existing pipe line main near at old science block and Near Cheyyeru sump to existing lateral lines (In View of Chief Minister Programme) at University Campus, Yogi Vemana University, Kadapa** - Permission to call for the quotations thorough University Web site - Request - Reg.

**Ref:-** Orders of the Hon'ble Vice Chancellor dated : 01-12-2018

-o0o-

The eligible firms/Contractors are requested to send their lowest quotation towards **“Providing pipe line from additional source to existing pipe line main near at old science block and Near Cheyyeru sump to existing lateral lines (In View of Chief Minister Programme) at University Campus, Yogi Vemana University, Kadapa”** the quotation should be addressed to the Registrar, Yogi Vemana University, Kadapa to reach this office on or before 04-12-2018.

S.No	Description of Item	Quantity	per	Rate	Amount
1	Supplying & fixing of 50 mm GI pipe Medium Grade properties & weight as per IS 1239 ISI mark for use of bore well in ground including cost of couplings, running joints, etc. including cost and conveyance of all materials and labour charges , ocomplete for finished item of work.				
A	50 mm nominal bore medium grade near sump	10.00	mts		
2	Supply and run of 3 of 36/0.3mm (2.5 Sq.mm) F.R.L.S P.V.C. insulated flexible copper cable in existing pipe for mains including all labour charges etc., complete.				
A	Near sump	60.00	Rmt		
3	Supply & Fixing of D.O.L Starter 415V, 3 phase, 50Hz.. enclosed with no volt coil and overload protection with necessary materials, etc., complete suitable upto 7.5.HP. Makes: Siemens / Crompton / L&T (MK2 DOL).	1	each		
4	Earth work excavation and depositing on bank with an initial lead and lift in all types of soils for pipe line trench of size 0.50x0.75 mts-75 mm dia and 0.7X1.00 - 90 mm dia including .cost and conveyance of pvc pie (Prince/Sudhakar/Kisan/Supreme or any ISI brand) 75 mm -4kg/sqm/ 90 mm - 6Kg/Sqm - and laying and jointing of PVC pipes.refilling of trench with excavated earth And all labour charges etc.complete.				

S.No	Description of Item	Quantity	per	Rate	Amount
A	PVC pipe line 90 mm dia (250X0.5X0.75)	250.00	Rmt		
B	PVC pipe line 75 mm dia (210X0.5X0.75)	210.00	Rmt		
5	Supply and Transportation of 5 HP, 3phase ISI self priming monoblock IP44 Motor pumpset <b>Makes:</b> Kumar / falcon / suguna .				
	monoblock motor	1.00	Each		
6	Supplying and fixing Gunmetal Gate (GM peet ) valve as per IS-778 Class - I , Indian make heavy type including cost and conveyance of all materials , labour charges , complete for finished item of work.				
A	50mm Nominal bore	2.00	Each		
Total					
Grand Total of Rs. With including GST @12%					
<b>Grand Total of Rs.</b>					

  
**REGISTRAR**  
**YOGI VEMANA UNIVERSITY**  
**KADAPA-516003.**

To

Copy to Web Committee, Yogi Vemana University, Kadapa with request to palce the call letter in University web site.  
Copy to the Notice Board  
Copy to file