

యోగి వేమన విశ్వవిద్యాలయం
YOGI VEMANA UNIVERSITY
 Vemanapuram, Kadapa - 516003, Andhra Pradesh, INDIA.
 (తన్నుతానెరిగిన తానెవో బ్రహ్మంయ :: If know thyself, Thou Art the Divinity)

ఆచార్య కె. చంద్రయ్య, M.Sc., M.Phil., Ph.D.,
 కులసచివులు
 Prof. K. Chandraiah, M.Sc., M.Phil., Ph.D.,
 REGISTRAR



☎ 08562 -225429
 Fax : 08562 -225419
 98858 07919
 94900 83127
 ✉ registrarvvu@gmail.com
 chandraiah2002@yahoo.co.uk
 kchandraiah@svuniversity.ac.in

No.YVU/ Engg.Dept/UE/JTO/Water supply pipe line at Net House & Glass House in
 YVU/web Quotation/2018-19 Dt. 22-02-2019

From
The Registrar
 Yogi Vemana University
 Kadapa

Sub:- Y.V.U- Engineering Section –Engineering Department- **Providing water supply pipe line connection to Net House and Glass House at Yogi Vemana University Campus, Kadapa (In view of Urgency)**– Permission to call for the quotations thorough University Web site - Request - Reg.

Ref:- Orders of the Hon'ble Vice Chancellor dated : 22-02-2019

-000-

The eligible Contractors/firms are requested to send their lowest quotation towards **“Providing water supply pipe line connection to Net House and Glass House at Yogi Vemana University Campus, Kadapa (In view of Urgency)”** the quotation should be addressed to the Registrar, Yogi Vemana University, Kadapa to reach this office on or before 26-02-2019.

S.No	Description of Item	Quantity	per	Rate	Amount
1.	Earth work excavation on bank with initial lead an lift in all soils for trenches for laying and jointing OD 28.60 mm CPVC pipes true to alignment and gradient and refilling the trench with excavated soils to bring the original surface and including the cost of CPV pipes etc. complete for finished item of work.	110.00	Rmt		
2.	Constructing 457.2 mm x 457.2 mm (1'6"x1'6") brick in CM 1:6 prop. Masonry. Inspection chamber upto 914.4 mm (3'0") and fitted with light weight 457.2 mm x 457.2 mm (1'6"x1'6") C.I frame and cover of 20 Kg including cost and conveyance of all materials like cement, sand, bricks, water etc., to site and all incidental and operational, labour charges like mixing cement mortar, constructing masonry, lift charges, curing , etc., complete for finished item of work as per Standard specification.	1.00	Each		
3.	Supplying and fixing Gunmetal Gate (GM peet) valve as per IS-778 Class - I , Indian make heavy type including cost and conveyance of all materials , labour charges , complete for finished item of work.	1.00	Each		
Total					
Extra GST @12%					
Grand Total of Rs.					

Further, the contractors/firms are requested to mention the GST Number in quotation otherwise the quotation stands cancelled.

The Registrar, Yogi Vemana University reserves the right to accept/reject/cancel any or all the quotations without assigning any reason thereof.


REGISTRAR
YOGI VEMANA UNIVERSITY
KADAPA-516003.

To

Copy to Web Committee, Yogi Vemana University, Kadapa with request to palce the call letter in University web site.
 Copy to the Notice Board
 Copy to file